



# QUOTE

Golden Grove Lutheran Primary School

**Date**  
27 Sep 2023

**Expiry**  
27 Oct 2023

**Quote Number**  
QU-1113S2

**Reference**  
QU-1113S2

**ABN**  
78 615 240 401

Climbing Tree Creations  
Pty Ltd  
16 Wilson Street  
ROYAL PARK SA 5014  
AUSTRALIA

## Quotation for the new playspace additions for Golden Grove Lutheran Primary School

### STAGE 2

Description	Quantity	Unit Price	GST	Amount AUD
Construction Preliminaries: Cost to prepare site specific documentation including works program, WHS documentation. Cost to supply temporary fencing, site bathroom facilities. Site mobilisation included.	1.00	3,165.00	10%	3,165.00
Play Space Audit: Cost to provide comprehensive play space Audit and documentation from an independent auditor as well as Climbing Trees in house compliance auditor.	1.00	1,600.00	10%	1,600.00
Earth Works: Cost to supply machinery including but not limited to: Tipper Truck, Excavator, Skid Steer and Skip Bins. Labour, dumpage and cartage cost are an inclusion.	1.00	7,310.00	10%	7,310.00
Rock and Log Edging (Pinned): Cost to supply and install rocks and logs to play space where required. Pinned edging will use smaller sized materials firmly secured on top of a compacted rubble base, screwed and bolted together.	10.00	295.00	10%	2,950.00
Rock and Log Edging (Mortared): Cost to supply and install rocks and logs to play space where required. Mortared edging will use larger materials mortared down to a reinforced strip footing.	12.00	420.00	10%	5,040.00
1. Rain Garden: This rain garden will address the existing drainage issues that are occurring on site. A 1m deep excavation that will be layered with an assortment of rock, gravel, sand and soils, wrapped in a permeable geo fabric and finished with a selection of native plants. This will be the target area for all drainage to be directed to.	1.00	27,976.00	10%	27,976.00

Description	Quantity	Unit Price	GST	Amount AUD
2. Low Log Balance: Supply and install extra large hardwood logs to form a bridge from one side of the rain garden to the other. Materials and labour included.	1.00	7,277.50	10%	7,277.50
3. Rock Steppers: Large boulders firmly secured in position that will act as either stepping stones or a place to sit.	6.00	476.60	10%	2,859.60
8. Stone grinding bowl: Locally sourced stone ground down into a bowl shape for potion making and various sensory experiences. Supply suitable, materials for grinding stone and labour. delivery and installation included.	2.00	1,247.50	10%	2,495.00
			Subtotal	60,673.10
			TOTAL GST 10%	6,067.31
			<b>TOTAL AUD</b>	<b>66,740.41</b>

### Terms

Please see document attached.  
Please sign and return contract to our office or via email.  
16 Wilson Street, Royal Park. SA. 5014  
info@climbingtree.com.au